

Responses to Questions for IFB # 1097  
Highland Residential Center (RC) Door Replacement at Building #29

|   |  |
|---|--|
| <b>Q1</b>                                     | <b>Please advise the required bid security, if any, for the referenced project.</b>  |
| A1  | Not required.  |
| <b>Q2</b>                                     | <b>Please advise the size of vision panel.</b>   |
| A2  | Size to be 5" wide x 20" high, Material as per Specification Section 088853 Security Glazing Part 2.02. See Drawing A104 for location / layout.  |
| <b>Q3</b>                                     | <b>Please advise a list of all hardware required to be removed and replaced. We also need this list to know how the doors to be prepped as this will affect the door's price.</b>  |
| A3  | See below listing:<br><br>1) One Lockset: Sargent 70-36-9251 less trim x WBX<br>2) Cylinder: BEST – IC Cylinder to suit x GMK<br>3) Stops, pulls: Rockwood – BF94DLL x 73L x RS-2-1353 x Torx // Mount flush - pull on push side of door. No cylinder holes. |
| Question Received at the Mandatory Site Visit |  |
| <b>Q4</b>                                     | <b>The existing frame need to have reinforcement for the new hinges, it does not show that on contract documents.</b>  |
| A4  | New hinges are to be the continuous type.<br>Assume Marker, Stanley - continuous hinge FM300 HT-Torx.<br>Assume no additional reinforcement required for bid purposes.   |